No.	Items of work	Unit	Rate	Quantity	Rate to be quoted in	
					Figures	Words
			Rs. a. p.			
3	Burnt stone jelly concrete in surki mortar ..	C.ft.	0 4 0	100		
4	Size stone in surki mortar	,,	0 4 0	75		
5	Burnt brick in surki morta	,,	0 4 6	50		
6	Burnt stone slabs one line dressed and fixed in surki mortar	S.ft.	0 4 6	100		
7	Plastering with surki mortar	Sqr.	3 8 0	5.00		
8	Cutting holes in the slabs	Each	0 10 0	2		
9	Providing plug and rod with locking arrangement	,,	12 0 0	1		

N. LAKSHMINARASIMIAH,
Executive Engineer

KOLAR DIVISION.

Notification dated 28th March 1940.

1. Sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M. on 22nd April 1940, for restoring Purahalli Devarkere, unrestored Major Tank. Reg. No. 257/681 of Kolar Taluk.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Kolar Division, should be addressed to the Executive Engineer, Kolar Division, in a sealed cover and superscribed as "Tender for restoring Purahalli Devarkere," The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a treasury chellan for earnest money of Rs. 295 paid to the treasury to the credit of "17(*a*) P. W. Deposits," against the account of the Executive Engineer, Kolar Division. The earnest money of the successful tenderer will be retained as security for the due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 22nd April 1940 at Kolar. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental schedule contract form, for the due fulfilment of the contract, and for the execution of all items of work in accordance with the Bombay Specifications. A reserve of 5 per cent will be withheld in the work bills of the contractor and the same repaid after the due fulfilment of the contract.

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Kolar, on all working days between 11 A.M. and 5 P.M.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same. When lumpsum provisions are shown in the schedule of quantities the contractor will be paid at either his tendered rate for each item or the prevailing schedule of rates in the Division at the discretion of the Executive Engineer.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to, and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions or additions, at the discretion of the Executive Engineer or his representative and may be due to any reasons whatsoever. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The works should be completed and handed over in a tidy condition to the Public Works Department by the end of June 1941, failing which the Executive Engineer may, at his discretion, levy a penalty of Rs. 5 per day which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—(*a*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.

(2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.

(3) Provide mortar mills and sheds, to keep materials under cover and also for workmen.

(4) Arrange for protecting work during inclement weather.

(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.

(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.

(7) Clean away all dirt rubbish, superfluous materials and debris as they accumulate.

(8) Provide arrangements for pumping and baling of water from excavations and foundations wherever and whenever necessary with his own pumping apparatus including necessary leading drains, slump pits, etc.

(9) Afford facilities to any other parties employed upon the work by the P. W. D. so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.

(10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary provide for the same by insurance at the proper time.

Note.—(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

N.B.—Copies of tenders in the prescribed form are obtainable from the Office of the Executive Engineer, Kolar Division, Kolar, only on a payment of four annas per form.

Abstract estimate for restoring Purahalli Devarkere unrestored Major Tank, Reg. No. 257—681 of Kolar Taluk.

No.	Items of work	Unit	Rate	Quantity	Rates to be tendered
	I. Bund.		Rs. a. p.		Rs.
1	Clearing thick jungle on the bund and removing roots, etc., complete ..	Grade	2 0 0	22	
2	Removing ant-hills and refilling same with sand and gravel	Each	0 8 0	30	
3	Cutting grips or trenches on the slope of bund ..	Grade	2 0 0	22	
4	Earthwork to bund with watering and consolidation	C.yd.	0 3 0	10,698	
5	New rough stone pitching one foot thick to bund	,,	0 8 0	1,556	
6	Removing and resetting (pitching) old stones with new jelly	S.yd.	0 2 9	1,250	
7	Gravel backing 6″ thick to pitching ..	C.yd.	0 6 0	468	
8	Turfing to bund	S.yd.	0 0 9	6,930	
9	Providing and fixing new grade stones including cutting figures and painting complete ..	Each	1 8 0	22	
10	Do Index stones do ..	No.	0 6 0	22	
11	Do Register No. and date stone do ..	,,	3 0 0	1	
	Do Gauge stone do ..	,,	15 0 0	1	
12	Gravelling the top of the bund including consolidation	C.yd.	0 6 0	249	
	Total Rs. ..				
	II. Sluice No. I.				
	Constructing a Cast Iron pipe sluice 6″ diar. at C. S. No. 4 with sill at R. L. 45.00.				
1	Cut opening the bund and refilling with watering and consolidation	L. S.	..	..	
2	Dismantling the existing sluice and stacking the materials	,,	..	..	
3	Earthwork excavation for foundation ..	C.yd.	0 2 6	4	
4	Concrete broken stone jelly in surki mortar ..	C.ft.	0 4 0	98	
5	Burnt size stone in surki mortar with bond stones	,,	0 4 6	151	
6	Providing, laying and jointing cast iron pipes 6″ diar. including Railway freight, cart-hire, hoisting, and etc., complete	R.ft.	2 8 0	36	
7	Burnt stone slab 6″ thick dressed and fixed in mortar	S.ft.	0 4 6	57	
8	Pointing with cement mortar after scraping joints	Sqr.	3 8 0	2.00	
9	Providing plug and rod with locking arrangements etc.	L. S.	..	..	
10	Cutting holes in slabs	No.	0 8 0	4	
	Total Rs. ..				
	III. Sluice No. II.				
	Constructing a Cast Iron pipe sluice 6″ diar. between C. S. No. 12 and 13 with sill at R. L. 45.00 (as per sluice No. I).				
	Total Rs. ..				

No.	Items of work	Unit	Rate	Quantity	Rates to be tendered
			Rs. a. p.		Rs.
	IV. Waste Weir.				
	Constructing a masonry waste weir 140 ft. long at the right flank with Crest at R. L. 50.00 at the site of natural escape.				
1	Earthwork excavation for foundation ..	C.yd.	0 2 6	227	
2	Stone jelly concrete in surki mortar	,,	0 4 0	609	
3	Burnt size stone in surki mortar with bond stones	C.ft.	0 4 6	1,777	
4	Pointing with cement after scraping joints ..	Sqr.	3 8 0	5.62	
5	Burnt stone slab 6" thick dressed and fixed in mortar..	S.ft.	0 4 6	240	
6	Providing joggle joints	No.	0 8 0	20	
7	Rough stone work new with jelly backing ..	C.yd.	1 8 0	213	
8	Providing gravel ramp in front of weir ..	,,	0 6 0	31	
9	Cutting high ground in rear to apron level for free flow of water and unforeseen	L. S.	..	..	
	Total Rs. ..				

C. R. IYENGAR,
Executive Engineer.

HASSAN DIVISION.

Notification dated 24th March 1940.

Sealed tenders will be received at the Office of the Executive Engineer, Hassan Division, Hassan, up to 12th April 1940 till 3 P.M., for constructing Electrical Building at Saklespur.

2. Tenders in the prescribed form obtainable in the Office of the Executive Engineer, Hassan Division, Hassan, should be addressed to the Executive Engineer, Hassan Division, Hassan, and should be superscribed as "Tender for constructing Electrical Building at Saklespur. The name of the tenderer should also be superscribed on the sealed cover.

3. Each tender must be accompanied by a deposit of Rs. 620 only in cash as earnest money. The earnest money of the successful tenderer will be retained as cash security for the due fulfilment of the contract. (Cash amount will not carry any interest). In case of the acceptance of the tender an addition of the five per cent of the estimated amount as security deposit should be paid at the time of executing the agreement in the Public Works Department.

4. The tenders will be opened in the presence of such tenderers who wish to be present on the date of opening. The final acceptance of the tenders will rest with the Superintending Engineer, Shimoga Circle, who does not bind himself to accept the lowest or any tender, or to assign any reasons whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Office of the Executive Engineer in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute the agreement in the departmental schedule contract form, for the due fulfilment of the contract.

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. Copies of contract documents, estimates and drawings may be seen at any time at the Office of the Executive Engineer, Hassan Division, Hassan, on all working days between 11 A.M. and 5 P.M.

8. Specific rates should be given for each item in the schedule and the rates should be in rupees, annas and pies and expressed in words and figures.

9. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates tendered should include all such lumpsum items.

10. No alterations which are made by the tenderers in the contract documents in the nomenclature of the sanctioned sub-heads will be recognised and if corrections are made, the tenders will be liable to rejection.

11. There should be no corrections or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

12. No reference should be made to the P. W. D. Current Schedule of Rates.